


THE UNITED REPUBLIC OF TANZANIA
MINISTRY OF WORKS, TRANSPORT AND COMMUNICATION



MULTINATIONAL: TANZANIA/BURUNDI: RUMONGE – GITAZA (45 KM) AND KABINGO – KASULU - MANYOVU (260.6 KM) ROAD UPGRADING PROJECT

UPGRADING OF KABINGO – KASULU- MANYOVU (260.6 KM) ROAD TO BITUMEN STANDARD,
LOT 2: KANYANI JUNCTION – MVUGWE SECTION (70.0 KM)

TENDER NO. AE/001/2018-19/HQ/W/103

Addendum No. 1 to the Bidding Documents

Date: 4th June 2019

Addendum No. 1 to the Bidding Documents is issued in accordance with Instructions to Bidders, Clause 8 to effect changes to the Bidding Documents.

Item No. 1

VOLUME 1A
Section II: Bid Data Sheet

ITB 14.8:

Replace

“Goods and Services to be procured wholly and exclusively for the purpose of execution of the Project may be exempted from taxes and duties in accordance with applicable laws of the United Republic of Tanzania.

Information on the Contractor's tax liabilities in the Client's country can be found from;

The Commissioner General,
Tanzania Revenue Authority (TRA),
TRA Headquarters Building,
Third Floor,
28 Edward Sokoine Drive,
11105 Mchafukoge, Ilala CBD,
P. O. Box 11491,
Dar Es Salaam.
Telephone: +255 22 2119591-4
Fax: +255 22 212 8593/6908”

Email: info@tra.go.tz
 website: www.tra.go.tz"

With

"Goods and Services to be procured wholly and exclusively for the purpose of execution of the Project including Contractor's Equipment and essential spare parts thereof, imported by the Contactor for the sole purpose of executing the contract, may be exempted from taxes and duties in accordance with applicable laws of Tanzania.

Hence, the rates and prices and the total Bid Price submitted by the Bidder should include all duties, taxes, and other levies payable by the Contractor under the Contract, or for any other cause, except taxes and duties for goods and services procured wholly and exclusively for the purpose of execution of the Project and Contractor's Equipment and essential spare parts thereof, imported by the Contactor for the sole purpose of executing the contract, which have been exempted under the applicable laws of Tanzania, as of the date 28 days prior to the deadline for submission of bids.

Bidders should contact the Tanzania Revenue Authority (TRA) for information on taxes and duties for goods and services, and equipment and spare parts thereof, which have been exempted.

Information on the Contractor's tax liabilities in the Client's country can be found from;

**The Commissioner General,
 Tanzania Revenue Authority (TRA),
 TRA Headquarters Building,
 Third Floor,
 28 Edward Sokoine Drive,
 11105 Mchafukoge, Ilala CBD,
 P. O. Box 11491,
 Dar Es Salaam.
 Telephone: +255 22 2119591-4
 Fax: +255 22 212 8593/6908
 Email: info@tra.go.tz
 website: www.tra.go.tz"**

Item No. 2.

Section VIII, Particular Conditions
Part B – Specific Provisions
 Page VIII-11

Replace:

The Contrat Price	14.1.1 (e)	Notwithstanding the provisions of subparagraph (b), Goods and Services to be procured wholly and exclusively for the purpose of execution of the Project may be exempted from taxes and duties in accordance with applicable laws of the United Republic of Tanzania.
-------------------	------------	---

With:

The Contrat Price	GC Clause 14.1	<p><i>Replace Sub-Clause 14.1.1 (b) with the following:</i></p> <p><i>The Contractor shall pay all taxes, duties, fees, levies and royalties required to be paid by him under the Contract <u>except</u> taxes and duties for goods and services procured wholly and exclusively for the purpose of execution of the Project and Contractor's Equipment and essential spare parts thereof, imported by the Contactor for the sole purpose of executing the contract, and which have been exempted under the applicable laws of Tanzania, and the Contract</i></p>
-------------------	----------------	---

		<p>Price shall not be adjusted for any of these costs except as stated in GC Clause 13.7 [Adjustments for Changes in Legislation].</p> <p>Sub-Clause 14.1.1 (e) is not applicable.</p>
--	--	---

Item No. 3

VOLUME 1A
SECTION IV: BIDDING FORMS

BOQ

Page IV-20

BILL 2000: DRAINAGE

SECTION 2300: CONCRETE KERBING, CONCRETE CHANNELLING, CHUTES AND DOWNPIPES, AND CONCRETE LININGS FOR OPEN DRAINS

Item 23.05 "(a) Outlet structure for concrete lined side drain" is amended to read:
"(a) Drop inlet structure for concrete lined side drain"

The amendment is reflected in the revised BOQ page attached herewith as Attachment 1 of **Addendum No. 1**. Hence, Bidders should replace the original page with the revised page.

Item No. 4

VOLUME 1A
SECTION IV: BIDDING FORMS

BOQ

Page IV-25

BILL 2000: BITUMINOUS LAYERS AND SEALS

SECTION 4200: BITUMINOUS BASE COURSE AND ASPHALT CONCRETE SURFACING

Item 42.02 "a) Asphalt concrete surfacing (Super pave type 12.5 with PG 70 – 10 binders) compacted thickness 50mm for carriageway" is amended to read:

"a) Asphalt concrete surfacing (Superpave type SP 12.5 with PG 70 – 10 binders) compacted thickness 50mm for carriageway and shoulders"

The amendment is reflected in the revised BOQ page attached herewith as Attachment 2 of **Addendum No. 1**. Hence, Bidders should replace the original page with the revised page.

Item No. 5

VOLUME 1A
SECTION IV: BIDDING FORMS

BOQ

Page IV-21

BILL 2000: DRAINAGE

SECTION 2300: CONCRETE KERBING, CONCRETE CHANNELLING, CHUTES AND DOWNPIPES, AND CONCRETE LININGS FOR OPEN DRAINS

Item 23.08 "(a) Cast in situ concrete lining for concrete side drain (class 20/20) 100mm thick including welded mesh" is amended to read "(a) Cast in-situ concrete lining for concrete side drain (class 20/20) 100mm thick including reinforcements as per Drawing No. NKM-EKE-DD-DR-D-00403"

The amendment is reflected in the revised BOQ page attached herewith as Attachment 3 of **Addendum No. 1**. Hence, Bidders should replace the original page with the revised page.

Item No. 6

VOLUME 1A

SECTION IV: BIDDING FORMS

BOQ

Page IV-33

BILL 6000B: STRUCTURES (BRIDGES)

SECTION 6600 NO-FINES CONCRETE, JOINTS, BEARINGS, PARAPETS AND DRAINAGE FOR STRUCTURES

Item 66.26B "Provide 75x75x8mm Equal Angle edge protection complete with 12mm mild steel rod anchors @ 1000mm c/c at expansion joints" is amended to read " Provide 75x75x8mm Equal Angle edge protection complete with 10mm mild steel rod anchors @ 600mm c/c at expansion joints"
The amendment is reflected in the revised BOQ page attached herewith as Attachment 4 of **Addendum No. 1**. Hence, Bidders should replace the original page with the revised page.

Item No. 7.

Section II: Bid Data Sheet

Pages II-iv to II-v:

<p>ITB 22.1</p> <p>Replace: "Date: 9th May 2019 Time: 10:00 hours local time"</p> <p>With: "Date: 3rd July 2019 Time: 10:00 hours local time"</p>
<p>ITB 25.1</p> <p>Replace: "Date: 9th May 2019 Time: Immediately after the deadline for bid submission."</p> <p>With: "Date: 3rd July 2019 Time: Immediately after the deadline for bid submission."</p>

Item No. 8.

VOLUME 1A

Section IV: Bidding Forms

Page IV-45

(i) Replace the Form of Tender Security (Bank Guarantee) with the form attached herewith as Attachment 5 of **Addendum No. 1**.

(ii) In the paragraph starting with the words "This guarantee will expire: (a) if the Bidder is", Bidders are allowed to insert a specific date under item (ii) to replace the words "twenty-eight days after the expiration of the Bidder's bid", if they wish. However, the date to be inserted must be 148 days from the deadline of submission of tenders.

Item No. 9

VOLUME 1A

SECTION IV: BIDDING FORMS

BOQ

Page IV-20

BILL 2000: DRAINAGE

SECTION 2300: CONCRETE KERBING, CONCRETE CHANNELLING, CHUTES AND DOWNPIPES, AND CONCRETE LININGS FOR OPEN DRAINS

Item 23.01 "(a) Precast, 180x280 concrete class 20/20 kerb as shown on drawing RD/KC/2/01 for **drainage control kerbs**" is amended to read:

"(a) Precast, 180x380 concrete class 25/20 kerb **for drainage control kerbs**"

Item 23.01 "(b) Precast, 180x280 concrete class 20/20 kerb as shown on drawing RD/KC/2/01 to **traffic islands, roundabouts, busbays etc**" is amended to read:

"(b) Precast, 180x380 concrete class 25/20 kerb **to traffic islands, roundabouts, busbays etc**"

The amendment is reflected in the revised BOQ page referred to above under **Item No. 3**.

Item No. 10

VOLUME 1A

SECTION VIII: Particular Conditions (PC)

Part A Contract Data.

Page VIII-5

Clause 14.5.3(c)(i)

Add "Bitumen" to the list of Plant and Materials for payment when delivered to the site.

The amendment is reflected in the revised page attached herewith as Attachment 6 of **Addendum No. 1**. Hence, Bidders should replace the original page with the revised page.

Item No. 11

VOLUME 1A

Section III: Evaluation and Qualification Criteria

Pages III-10 to III-13: The requirements on Key Activities is hereby amended for consistency with other lots. Hence replace the pages with those attached as Attachment 7 of **Addendum No. 1**

Item No. 12

VOLUME 1A

SECTION IV: BIDDING FORMS

BOQ

Page IV-20

BILL 2000: DRAINAGE

SECTION 2300: CONCRETE KERBING, CONCRETE CHANNELLING, CHUTES AND DOWNPIPES, AND CONCRETE LININGS FOR OPEN DRAINS

Item 23.06 "(a) Concrete slabs for crossing side drains (class 20/20) with class U2 surface finish" is amended to read:

"(a) Concrete slabs for crossing side drains (class 25/20) with class U2 surface finish"

The amendment is reflected in the revised BOQ page referred to above under **Item No. 3**.

Item No. 13

VOLUME 1A

SECTION IV: BIDDING FORMS

BOQ

Page IV-12

LOT 2: GRAND SUMMARY OF BILL OF QUANTITIES

Replace the Lot 2 BOQ Grand Summary page in the hardcopy with that attached herewith as Attachment 8 of Addendum No. 1.

The following additional amendment to the Bidding Documents applies:

Item No. 14

VOLUME 1A

Section II: Bid Data Sheet

ITB 7.1:

Replace

"Requests for clarifications should be received by the Employer no later than **21 days**, prior to the deadline for submission of Bids."

With

"Requests for clarifications should be received by the Employer no later than **14 days**, prior to the deadline for submission of Bids."

ATTACHMENTS TO ADDENDUM NO. 1

**[LOT 2: KANYANI JUNCTION - MVUGWE SECTION (70.5 KM)
TENDER NO. AE/001/2018-19/HQ/W/103]**

Upgrading of Kabingo – Kasulu – Manyovu (260.6 Km) Road to Bitumen Standard, Lot 2: Kanyani Junction –
Mvugwe Section (70.5 Km), Tender No. AE/001/2018-19/HQ/W/103

Attachment 1 of Addendum No. 1

Upgrading of Kabingo – Kasulu – Manyovu (260.6 Km) Road to Bitumen Standard, Lot 2: Kanyani Junction –
Mvugwe Section (70.5 Km), Tender No. AE/001/Z 18-19/HQ/W/103

BILL No. 2000: DRAINAGE

ITEM	DESCRIPTION	UNIT	QUANTITY	RATE (TZS)	AMOUNT (TZS)
	Brought Forward				
22.23	Service Ducts:				
	(ii) 300 mm dia PVC class PN4	m	450		
22.24	Duct marker blocks as shown on drawing	No.	40		
<u>SECTION 2300: CONCRETE KERBING, CONCRETE CHANNELLING, CHUTES AND DOWNPIPES, AND CONCRETE LININGS FOR OPEN DRAINS</u>					
	-				
23.01	Concrete kerbing: (with class 20/20 concrete - complete with concrete class 15/20 haunching, foundation (bedding), mortar as specified).				
	(a) Precast, 180x380 concrete class 25/20 kerb as shown on drawing RD/KC/2/01 for drainage control kerbs	m	24,544		
	(b) Precast, 180x380 concrete class 25/20 kerb as shown on drawing RD/KC/2/01 for kerbs to traffic islands, roundabouts, busbays etc	m	3,250		
23.03	Concrete chutes (typical designs):				
	() Prefabricated down chutes at high fills	m	500		
23.05	Inlet, outlet, transition and similar structures (typical designs):				
	(a) Drop inlet structure for concrete lined side drain	No	150		
	(b) Outlet structure for concrete down chute at high fills	No	100		
	(c) Inlet structure for concrete down chutes at high fills	No	100		
23.06	Inlet, outlet transition and similar structures (measured by components):				
	(a) Concrete slabs for crossing side drains (class 20/20) with class U2 surface finish	m ³	30		
	Carried Forward				

U...ding of Kabingo – Kasulu- Manyovu (260.6 Km) Road to Bitumen Standard, Lot 2: Kanyani Junction - Mvugwe (70.5 Km) Section

Attachment 2 of Addendum No. 1

Upgrading of Kabingo – Kasulu – Manyovu (260.6 Km) Road to Bitumen Standard, Lot 2: Kasulu Junction –
Mvugwe Section (70.5 Km), Tender No. AE/001/2018-19/HQ/W/103

SECTION 4000: BITUMINOUS LAYERS AND SEALS

ITEM	DESCRIPTION	UNIT	QUANTITY	RATE (TZS)	AMOUNT (TZS)
SECTION 4100: PRIME AND CURING MEMBRANES					
41.01	Prime coat:				
	(a) MC-30 cut-back bitumen (Supply, heat and apply prime coat of MC-30 cut-back bitumen, at the rate of 0.8 - 1.0 litres/m ² including aggregate blinding as approved)	litre	845,300		
SECTION 4200: BITUMINOUS BASE COURSE AND ASPHALT CONCRETE SURFACING					
42.02	(a) Asphalt concrete surfacing:				
	a) Asphalt concrete surfacing (Superpave type SP 12.5 with PG 70 - 10 binders) compacted thickness 50mm for carriageway and shoulders	m ³	42,800		
	(b) Bitumen for asphalt concrete surfacing PG 70 -10 performance grade bitumen	t	4,794		
42.03	Tack coat of 57% stable grade bitumen emulsion at 0.4litres/m ²	litre	341,800		
4000	TOTAL CARRIED TO SUMMARY				

Attachment 3 of Addendum No. 1

Upgrading of Kabingo – Kasulu – Manyovu (260.6 Km) Road to Bitumen Standard, Lot 2: Kanyani Junction –
Mvugwe Section (70.5 Km), Tender No. AE/001/2018-19/HQ/W/103

BILL No. 2000: DRAINAGE

ITEM	DESCRIPTION	UNIT	QUANTITY	RATE (TZS)	AMOUNT (TZS)
	Brought Forward				
23.07	Trimming of excavations for concrete-lined open drains: (For trapezoidal and rectangular drain's bottom inverts lined with in-situ concrete)				
	(a) In soft material as defined in clause 3603	m ²	26,355		
	(b) In rock as defined in clause 3603	m ²	2,636		
23.08	Concrete lining for open drains:				
	((a) Cast in situ concrete lining for concrete side drain (class 20/20) 100mm thick including reinforcement as per Drawing No. NKM-EKE-DD-DR-D-00403	m ³	1,350		
	(b) Class U2 surface finish to cast in situ concrete for concrete side drain	m ²	26,355		
23.13	Polyethylene sheeting (0.15 mm thick) for concrete-lined open drains	m ²	26,355		
<u>SECTION 2500: PITCHING, STONEMWORK AND PROTECTION AGAINST EROSION</u>					
25.01	(b) Stone pitching:				
	(a) Grouted stone pitching; 200mm total thickness	m ²	3,360		
25.02	Ripap				
	(a) Packed riprap minimum size 400mm	m ³	100		
25.08	Erosion checks to ditch type B1 as shown on the drawing	No	770		
<u>SECTION 2600: GABIONS</u>					
26.01	Foundation trench excavation and backfilling for gabions:				
	(a) In solid rock as defined in clause 3603	m ³	150		
	(b) In all other material other than rock as defined in clause 3603	m ³	1000		
	Carried Forward				

Upgrading of Kabingo – Kasulu- Manyovu (260.6 Km) Road to Bitumen Standard, Lot 2: Kanjani Junction - Mvugwe (70.5 Km) Section

Attachment 4 of Addendum No. 1

Upgrading of Kabingo – Kasulu – Manyovu (260.6 Km) Road to Bitumen Standard, Lot 2: Kanyani Junction – Mvugwe Section (70.5 Km), Tender No. AE/001/2018-19/HQ/W/103

SECTION 6000B: REINFORCED CONCRETE BRIDGE STRUCTURES

ITEM	DESCRIPTION	UNIT	QUANTITY	RATE (TZS)	AMOUNT (TZS)
	Brought Forward				
	(d) Provide handrail with 125x75x8mm RHS support posts @ 2000mm c/c, with 1no. 50mm & 4no. 40mm diameter CHS as horizontal rails in between the posts as per drawing details.	m	82		
	(e) Provide balustrade of ARMCO flex beam with 124x75x8mm rectangular hollow section (RHS) support posts @ 2000mm c/c bedded in shoulders	m	70		
	(f) Provide 6No. 150mm diameter service pipes to sides of slab within the walkway	m	245		
66.19B	Drainage pipes and weep holes:				
	(a) Provide 2.4m long 75mm diameter Class C PVC drainpipe to deck slab at both kerbs at 3000mm c/c (max) to deck slab at both kerbs at 3000mm c/c (max)	No.	18		
	(b) Provide 2.0m long, 75mm diameter class C pvc pipes as weep holes @1500 c/c on to abutments and walls	No.	32		
	(c) Provide 1.8m long 75mm diameter Class C PVC drainpipe to deck slab at both kerbs at 1500mm c/c (max)	No.	32		
66.21B	(a) Geotextile filter fabric to wall (as terram 280g/m ² or approved equivalent.	m ³	480		
66.22B	Apply two coats of bituminous water-proofing paint to backs of abutments and wingwalls	m ²	1,770		
66.23B	Provide 1.8m long 75mm diameter Class C PVC drainpipe to deck slab at both kerbs at 1500mm c/c (max)	No.	20		
66.24B	Provide 300x300x6mm plate welded to 1400mm long, 32mm diameter stainless steel dowel bar grouted into abutment with 35mm dia PVC sleeve to receive deck girders.	No.	22		
66.25B	600mm long R25 dowel anchored into approach slab and as shown in details, covered with 30mm PVC class E sleeve	No.	85		
66.26B	Provide 75x75x8mm Equal Angle edge protection complete with 10mm mild steel rod anchors @ 600mm c/c at expansion joints	m	55		
	Carried Forward				

Attachment 5 of Addendum No. 1

Upgrading of Kabingo – Kasulu – Manyovu (260.6 Km) Road to Bitumen Standard, Lot 2: Kanyani Junction –
Mvugwe Section (70.5 Km), Tender No. AE/001/2018-19/HQ/W/103
