


THE UNITED REPUBLIC OF TANZANIA
MINISTRY OF WORKS, TRANSPORT AND COMMUNICATION



UPGRADING OF MKANGE- TUNGAMAA- PANGANI ROAD (120.8 KM) INCLUDING PANGANI BRIDGE (525M) TO BITUMEN STANDARD, LOT 3: TUNGAMAA- MKWAJA-MKANGE (95.2 KM) INCLUSIVE OF 3.7KM OF SPUR ROAD TO KIPUMBWI

TENDER NO. AE/001/2019-20/HQ/W/34

Clarification No. 1 to the Bidding Documents

Date: 7th August 2020

Clarification No. 1 to the bidding document is issued in accordance with Instructions to Bidders, Sub-Clause 7.1 of the Bidding documents as follows: -

S/N	Issues/Questions	<i>Employer's Responses</i>
1.	"PCC Clause: 8.7.1- "Delay Damages Delay Damages for the works - 0.5% of the Contract Price per week in the currencies and proportions in which the contract price is payable." We request to consider value of balance works in the place of contract price for calculation of delay damages.	<i>Bidders are required to abide to the requirements of the Bidding Documents.</i>
2.	"GCC Clause: 14.1, ITB Clause: 14.8: Taxation" ITB Clause 14.8 Hence, the rates and prices and the total Bid Price submitted by the Bidder should include all duties, taxes, royalties and other levies payable by the Contractor under the Contract, or for any other cause, except taxes and duties for goods and services procured wholly and exclusively for the purpose of execution of the Project and Contractor's Equipment and essential spare parts thereof, imported by the Contactor for the sole purpose of executing the contract, which have been exempted under the	<i>The Total Bid Price shall include all Contractor's tax liabilities as stipulated in BDS 14.8 of the Bidding Documents. All matters related to Taxes shall be referred to the Commissioner General, Tanzania Revenue Authority (TRA) and the Commissioner of Minerals, Ministry of Minerals for further clarifications through</i>

S/N	Issues/Questions	Employer's Responses
	<p>applicable laws of Tanzania, as of the date 28 days prior to the deadline for submission of bids.</p> <p>GCC clause 14.1 The Contractor shall pay all taxes, duties and fees required to be paid by him under the Contract, and the Contract Price shall not be adjusted for any of these costs except as stated in GC Clause 13.7 [Adjustments for Changes in Legislation]; "As per clause 14.8 of ITB taxes and duties for goods, services and Contractor's Equipment & spare parts procured for the purpose of project are exempted.</p> <p>As per GCC Contractor shall pay all taxes and duties.</p> <p>Please clarify the ambiguity and provide us the Goods and services for which taxes are exempted"</p>	<p><i>addresses provided in BDS 14.8 of the Bidding Documents.</i></p>
3.	<p>"PCC Clause: 14.3.2: Retention Money Percentage of retention money-10% Limit of retention money-5% of accepted contract amount." "As the total limit of retention money is 5%, we request you to modify the Percentage of retention money to 5%.</p> <p>Also, we hereby request you to accept an upfront Bank guarantee towards retention money and not deduct Retention money in cash from interim payments."</p>	<p><i>Bidders are required to abide to the requirements of the Bidding Documents.</i></p> <p><i>The proposal is not acceptable. Bidders are required to abide to the requirements of the Bidding Documents.</i></p>
4.	<p>"PCC Clause: 14.6.2": Minimum amount of Interim Payment Certificates. 2% of accepted contract amount."We request you to reduce this Minimum amount of IPC to 1%, as this will affect the cash flow at the start of project.</p>	<p><i>The proposal for reduction of minimum amount of IPC from 2% to 1% is not acceptable. Bidders are required to abide to the requirements of the Bidding Documents.</i></p>
5.	<p>"GCC Clause: 14.7. "Payment The amount certified in each Interim Payment Certificate within 56 days after the Engineer receives the Statement and supporting documents; or, at a time when the Bank's loan or credit (from which part of the payments to the Contractor is being made) is suspended, the amount shown on any statement submitted by the Contractor within 14 days after such statement is submitted, any discrepancy being</p>	<p><i>Bidders are required to abide to the requirements of the Bidding Documents</i></p>

S/N	Issues/Questions	Employer's Responses
	<p>rectified in the next payment to the Contractor."</p> <p>We request you to provide 80% interim payment within 7 days of submission of statement to the Engineer and remaining 20% shall be paid within 56 days after submission of statement to Engineer.</p>	
6.	<p>"Special Specifications SS1202 "Utility Shifting The Contractor shall inform utility authorities of the start of the Works at least two months before start of work at a particular section in order for the utility authorities to show the Contractor locations of their services.</p> <p>The Contractor shall work in close cooperation with private owners or public authorities controlling services, which have to be protected, moved or relocated. Consultations and negotiations regarding the alterations of services shall have to commence as soon as the Contractor is given possession of Site. Details regarding such negotiations concluded between the Contractor and the owners shall be notified to the Engineer on the day of commencement of Works. Should the owners of services refuse to cooperate with the Contractor in a reasonable manner in connection with the protection or moving of services belonging to them, the Contractor shall refer the matter to the Engineer.". "It is understood that if any utility shifting need to be done by the contractor, the same shall be paid separately.</p> <p>Please clarify</p>	<p><i>Item 12.02(a) of the BoQ covers relocation of utilities and it has a Provisional sum for utility owners to relocate various utilities which will be affected by road construction.</i></p> <p><i>"The removal of existing utilities required to permit orderly progress of work will be accomplished by local agencies, unless otherwise shown on the Drawings. Whenever a telephone or telegraph pole, pipeline, conduit, sewer, or other utility is encountered and must be removed or relocated, the Contractor shall advise the proper local authority or owner and arrange for its removal".</i></p>
7.	<p>"Kindly please clarify the Land acquisition status for the project 1> Total Land required for the project 2> Land already acquired by TANROADS 3> Balance land yet to be acquired by TANROADS"</p>	<p><i>All land to be permanently used or occupied by the Works will be provided by the Employer, but the approval of the Engineer must be sought before entry upon the land". The Employer has an obligation to ensure that the Contractor is given access to the site prior works commencement.</i></p>
8.	<p>We request you to kindly please issue a copy of the standard specifications along with the bid documents</p>	<p><i>The Standard Specifications are not reproduced, as they are protected by copyright. Bidders are required to</i></p>

S/N	Issues/Questions	Employer's Responses
		<p>contact Central Materials Laboratory (CML) to obtain original copy on the following address: -</p> <p>Central Materials Laboratory (CML), P.O. Box 9452, Dar es Salaam. Tel: +255 22 2866122 Fax: +255 22 2866088 E-mail: cml@tanroads.go.tz</p>
9.	<p>Schedule of Adjustment Data "Section IV (Pg 62), Table Bidding Forms Local Currency: Please provide website or publication where indices for materials/items in Table - A are published and are acceptable to the Employer.</p> <p>Due to the ongoing Pandemic, it is difficult for the bidders to collect the locally published indices, request you to please upload the same for the reference of the bidders "</p>	<p><i>It is a bidder's obligations to identify sources and indices of materials to be used for construction.</i></p>
10.	<p>Schedule of Adjustment Data: "Clause - If a price adjustment is applied to payments made in a currency other than the currency of the sources of the index for a particular index input, a correction factor Z_0/Z will be applied to the respective component factor of P_n for the formula of the relevant currency. Z_0 is number of units of the currency of the country of the index, equivalent to one unit of the currency of payment on the date of the base index, and Z is the corresponding number of such currency units on the date of the current index</p> <p>Query :- Kindly please elaborate the above clause with an example for better clarity of the bidders"</p>	<p><i>It is a Bidder's obligations to be familiar with the requirements of the Bidding Documents.</i></p>
11.	<p>Engineers Facilities, SS 1400 "Please consider land being provided to the Contractor, free of cost, for road diversions and land for Engineer's facilities and for Contractors own facilities like accommodation, laboratory, working areas etc., to avoid delays to the project."</p>	<p><i>Land for diversions and Engineer's facilities will be provided by the Employer. But the Contractor is obliged to acquire land for his facilities.</i></p>
12.	<p>Engineers Facilities, SS 1400 "Please provide the detailed drawings and plans for the Engineers facilities.</p> <p>Please upload Drawing No.</p>	<p><i>Drawing No. 106784/T/DS/C501/C502/C503/C504/C505/C506 has provided. Refer Item No. 2 of Addendum No. 5 -</i></p>

S/N	Issues/Questions	Employer's Responses
	106784/T/DS/C501/C502/C503/C504/C505/C506 for the reference of the bidders."	Appendix 3
13.	<p>Item No. 23.05 "Please provide the details of the inlet / outlet structures</p> <p>Please upload Drawing No. 106784/T/DS/C203/C204/C205/C206/C207/C208 for the reference of the bidders"</p>	<p>The missing Drawing details showing inlet/outlet structure is provided. Refer Item No. 2 of Addendum No. 5 – Appendix 1</p>
14.	<p>Side Drains / Urban Side Drains "Please provide the details of the Side Drains & Urban Side Drains</p> <p>Please upload Drawing No. 106784/T/DS/C211/C212 for the reference of the bidders"</p>	<p>The missing typical drawings for side drains are provided. Refer Item No. 5 of Addendum No. 2 – Appendix 1</p>
15.	<p>Kerbing Details "Please provide the details of the Kerbs to be provided</p> <p>Please upload Drawing No. 106784/T/DS/C308 for the reference of the bidders"</p>	<p>Kerb stone details is provided. Refer Item No. 5 of Addendum No. 2 – Appendix 1</p>
16.	<p>Guardrail Details "Please provide the details of the Guardrails to be provided</p> <p>Please upload Drawing No. 106784/T/DS/C309 for the reference of the bidders"</p>	<p>The missing Guardrail Details is provided. Refer Item No. 5 of Addendum No. 2 – Appendix 1</p>
17.	<p>Speed Hump Details "Please provide the details of the Speed humps to be provided</p> <p>Please upload Drawing No. 106784/T/DS/C310/C311 for the reference of the bidders"</p>	<p>The missing Speed Hump Details is provided. Refer Item No. 5 of Addendum No. 2 – Appendix 1</p>
18.	<p>CI 14.2.1 , Particular Conditions "The Clause states that ""The total advance payment, the number and timing of instalments (if more than one), and the applicable currencies and proportions, shall be as stated in the Particular Conditions""</p> <p>We understand that the entire Advance payment will be made in 1 Installment at the beginning "</p>	<p>Yes. The entire Advance payment will be made to the Contractor in one Installment at the beginning upon meeting the pre-requisite conditions.</p>
19.	<p>Material Report Kindly please clarify whether the Hardstone sites indicated in the report are Government lands or Private Lands</p>	<p>Pay Item 12.01(a) has a provisional sum for acquisition of land for borrow pits and quarries in cases where the same are not owned by the Government. In addition, Bidders' attention is</p>

S/N	Issues/Questions	Employer's Responses
		drawn to Clause 3403 of the Standard Specifications for Road Works, 2000 of Ministry of Works
20.	<p>SS.1402 FACILITIES FOR THE ENGINEER: ENGINEER'S STAFF HOUSES, OFFICES AND LABORATORY.</p> <p>The Clause States that "The houses, offices and laboratory, including all required equipment are to be handed over to the Engineer in full habitable condition not later than 3 (three) months from the date of the order to commence work."</p> <p>1) Kindly please extend the completion period to 6 months from the date of order to commence work, as the procurement of the material and its installation at site will require some time"</p>	Bidders are required to abide to the requirements of the Bidding Documents
21.	Borrow Areas / Hard Stone Areas. We understand that the land for quarries, borrow pits as indicated in the material report will be made available by the Employer free of cost. Please Clarify whether any new quarry site identified by the contractor apart from those indicated in the material report will also be available free of cost	Refer to Clause 1215 of the Standard Specifications for Road Works 2000 of the Ministry of Works.
22.	BOQ Item NO. 38.02. Kindly please confirm if the availability of material class C1 type is as per the material report attached with the tender docs and the same will be available within the project corridor	The Materials Report is provided for information only. It is the Contractor's obligations to confirm the provided information and look for other sources of materials.
23.	Bridge @ Km 111+860. As the Bridge is over an existing railway line. We understand that all the permissions, approvals and coordination with the railways department will be done by the Client and Contractor will not be responsible for the permissions and coordination with the railways	Requests for permissions will be prepared and submitted to the relevant Authorities by the Contractor through the Engineer and copied to the Employer for information and follow up.
24.	BOQ Item NO. 64.02 (a)/(b) - Manufacturing precast concrete members: We understand that the BOQ item price is inclusive of Concrete, Reinforcement, High tensile steel. Please Clarify	Yes, they are all inclusive.
25.	We request you to kindly please extend the bid due date by 30 days to enable to prepare a competitive bid	The Bids submission date is extended from 14th August 2020 to 14th September 2020 . Please Refer

S/N	Issues/Questions	Employer's Responses
		Addendum No. 1 dated 3 rd August 2020 and Item No. 6 of Addendum No. 2
26.	<p>According to 2.1.5 in the Bidding Procedures Section III. Evaluation and Qualification Criteria, Qualification Tables (Without Prequalification n) of the Tendering Document.</p> <p>The Ineligibility based on a United Nations resolution or Borrower 's country law in the Qualification Tables (Without Prequalification) is not reflected in the relevant terms of the Letter of Bid</p>	<p><i>The ineligibility based on a United Nations resolution or Borrower's country law is reflected in Item (k) of Letter of Bid. Also, Bidders' attention is drawn to the requirements of ITB 4.4 to 4.8 of the Bidding Documents.</i></p>
27.	<p>According to 2.4 in the Bidding Procedures Section III. Evaluation and Qualification Criteria, Qualification Tables (Without Prequalification) of the Tendering Document</p> <p>Can the subsidiary personnel performance be used as the company's personnel performance?</p> <p>What should we do because there is no description on the list of performance (not specifically reflected in the domestic notice of award and notice of completion)</p> <p>According to Personnel in Section III: Evaluation and Qualification Criteria of the Tendering Document.</p> <p>What qualifications we need to provide because there is no similar position here as the environmental and social manager specified in the tendering document</p>	<p><i>The question is not clear</i></p> <p><i>The required qualifications for each key staff are provided in Item 2.5 of Section III: Evaluation and Qualification Criteria of the Tendering Document.</i></p>
28.	<p><i>The design of spur roads are not provided in the bid document.</i></p>	<p><i>Plan and profile drawings for approach roads are provided. Refer Item No. 5 of Addendum No. 2 – Appendix 4.</i></p> <p><i>However, Only preliminary design was carried out and the BoQ includes scope of Works but details will be provided by the Supervision Consultant during the execution.</i></p>
29.	<p><i>Start and end chainages of the project are not clear identified in the bid documents.</i></p>	<p><i>Lot 2 starts at Tungamaa and ends at Pangani Bridge (km</i></p>

S/N	Issues/Questions	Employer's Responses
		164+750 to 179+050) and it includes the Pangani Bridge. Lot 3 starts at Mkwaja to Tungamaa (km 73+250 to 164+750).
30.	There is contradiction regarding soil stabilization (C1, C2) in the document whether it should be done on site (in situ) or be done in Plant	Bidders' attention is drawn to SS 3803 of the Special Specifications.
31.	In the soft copies provided for Road cross section some of the drawings for cross sections were labelled REJECTED. What does that mean?	Drawings labelled "REJECTED) shall not form part of the Bidding Documents. Drawings labelled "REJECTED) shall not form part of the Bidding Documents. Bidders are advised to ignore them. Correct drawings are provided. Refer Item No. 5 of Addendum No. 2 – Appendix 2
32.	Confusion of start of the project between the name of project and Lots	Please refer Clarification No. 29 above.
	SERIES 2100	
33.	Item 21.12 Concrete outlet structures, manhole boxes, junction boxes and cleaning eyes for subsoil drainage: (a)(b)(c)(d) No drawing was found in the Book of Drawings, Volume 2, Bidding Documents.	The missing Drawing details showing Concrete outlet structures, manhole boxes, junction boxes and cleaning eyes for subsoil drainage is provided. Refer Item No. 2 of Addendum No. 5 – Appendix 1
34.	Item 21.13 Concrete caps for subsoil drain pipes No drawing was found in the Book of Drawings, Volume 2, Bidding Documents.	The missing Drawing details showing Concrete caps for subsoil drain pipes is provided. Refer Item No. 2 of Addendum No. 5 – Appendix 1
	SERIES 2300	
35.	Item 23.05 Inlet, outlet, transition and similar structures (typical designs): (a)(b)(c) No drawing was found in the Book of Drawings, Volume 2, Bidding Documents.	The missing Drawing details showing Inlet, outlet, transition and similar structures (typical designs) is provided. Refer Item No.5 of Addendum No. 2 –Appendix 1
36.	Item 23.12 Steel reinforcement: (c) Welded steel fabric	Refer to clause 6302(b) of the standard specifications for Road Works, 2000 of Ministry

S/N	Issues/Questions	Employer's Responses
	No Grade and type was indicated in the BOQ, Volume 1, Bidding Documents.	<i>of Works.</i>
37.	Item 23.15 Precast concrete blocks in outlet structures No drawing was found in the Book of Drawings, Volume 2, Bidding Documents.	<i>The missing Drawing details showing Precast concrete blocks in outlet structures is provided. Refer Item No. 5 of Addendum No. 2 - Appendix 1</i>
38.	Item 23/B 24.01 Asphalt berm: (c) Placed at guardrails No drawing was found in the Book of Drawings, Volume 2, Bidding Documents.	<i>Asphalt berm details is provided. Refer Item No. 5 of Addendum No. 2 - Appendix 1</i>
	SERIES 2500	
39.	Item 25.01 Stone Pitching (a)(b) No thickness was indicated in the Book of Drawings, Volume 2, Bidding Documents.	<i>The thickness of the stone pitching, measured at right angles to the surface, shall not be less than 200 mm.</i>
	SERIES 5500	
40.	Item 55.07 Re-establishing the painting unit at the end of the Defects Liability Period Please confirm if the Contractor needs to Re-establish the whole road marking works.	<i>Yes, will road markings will be re-established for the entire road as specified in the pay item.</i>
41.	Item 55.1 Road hump as shown on the Drawings No drawing was found in the Book of Drawings, Volume 2, Bidding Documents.	<i>The missing Drawing details showing Road hump is provided. Refer Item No. 5 of Addendum No. 2 - Appendix 1.</i>
42.	Item 55.11 Speed reducing rumble strips as shown on the Drawings No drawing was found in the Book of Drawings, Volume 2, Bidding Documents.	<i>The missing Drawing details showing Speed reducing rumble strips is provided. Refer Item No. 5 of Addendum No. 2 - Appendix 1.</i>
	Bill B2: Structure Construction	
43.	Item 61.03 Access and drainage: (a) Access Please confirm the purpose and location of Access.	<i>The bid lump sum shall include full compensation for providing access, which, inter alia, shall include constructing temporary banks, artificial islands and/or cofferdams, their protection, safeguarding and maintenance draining and keeping dry the working areas and draining the excavations within the access, and any incidentals in</i>

S/N	Issues/Questions	Employer's Responses
		<p>respect of work to be done below standing water. 75% of the lump sum will be paid when the access has been constructed. The remaining 25% will be paid after the access has been removed.</p>
44.	<p>Item 63.01 Steel reinforcement for: (a) (iii) Welded steel fabric</p> <p>No Grade and type was indicated in the BOQ, Volume 1, Bidding Documents.</p>	<p>Refer to clause 6302(b) of the standard specifications for Road Works, 2000 of Ministry of Works.</p>
45.	<p>Item 66.14 Dowels/guides (Y16 Galvanised)</p> <p>No length was indicated in the BOQ, Volume 2, Bidding Documents.</p>	<p>Dowels shall have a diameter 20mm with 600mm length @ 200mm centres spacing.</p> <p>Tie bars have a 12mm diameter with 600mm length @300mm centres spacing.</p>
46.	<p>Item 66.15 Concrete parapets</p> <p>No drawing was found in the Book of Drawings, Volume 2, Bidding Documents.</p>	<p>Item 66.15: concrete parapets is not required. Refer Item No. 2 of Addendum No. 2</p>
47.	<p>Item 91.01 Cladding panels: (a) Concrete Cladding panels</p> <p>No drawing was found in the Book of Drawings, Volume 2, Bidding Documents.</p>	<p>Items 91.01 – 91.01 are not required. Refer Item No. 3 of Addendum No. 2</p>
48.	<p>Item 91.08 Supply of precast concrete coping units</p> <p>No drawing was found in the Book of Drawings, Volume 2, Bidding Documents.</p>	<p>Please refer to Clarification No. 47 above.</p>
49.	<p>Item: "Section III, Evaluation and Qualification Criteria, 2.4.2 b-1), (iii) Construction of Bituminous Pavement Works – 60,000 m³ per year for any of the Contracts"</p> <p>It is noticed that this requires a Contractor has successfully implemented at least one single Contract with 60,000 m³ Bituminous Pavement Works completed in single year only, which is obviously too high to a project and impractical in implementation. Please confirm if this requirement is correct.</p>	<p>The Employer has considered the Bidder's observation and the production rate has been reduced from 60,000m³ to 45,000m³. Refer Item No. 4 of Addendum No. 2</p>
50.	<p>There is no detailed structural drawing for concrete outlet structure, manhole box, connection box, cleaning hole and concrete cover of the underground drainage system in</p>	<p>Please refer to Clarification No. 33 above.</p>

S/N	Issues/Questions	Employer's Responses
	the drawing of W.34-Lot 3, please provide it.	
51.	There is no detailed structural drawing for pipe culvert, underground drainage system, curb, revetment, gabion, etc in the drawing of W.34-Lot 3, please provide it.	<i>Structural drawing for pipe culvert, underground drainage system, curb is provided. Refer Item No. 5 of Addendum No. 2 – Appendix 1</i>
52.	There is no drawing of cross section for box culvert excavation in the drawing of W.34-Lot 3, please provides it.	<i>The provided information in the bidding documents is sufficient for bidders to price the bid.</i>
53.	There is only detailed drawing of signboard, no sign pole and foundation for traffic safety work in the drawing of W.34-Lot 3, please provide it.	<i>Details of sign pole and foundation is provided. Refer Item No. 5 of Addendum No. 5 – Appendix 1</i>
54.	There is no detailed drawing of dismantling existing pipe culvert, box culvert and Bridge in the drawing of W.34-Lot 3, and whether the quantities are estimated temporary?	<i>No drawings for existing pipe culvert is provided. Bidders are required to visit the site and establish the actual works and price accordingly in Item 32.01 of the BoQ.</i>
55.	The building construction method and construction material are unknown, please clarify it.	<i>The question is not clear</i>
56.	There is no detailed description for the foundation below the ground of the building, please clarify it.	<i>The question is not clear</i>
57.	There is no relative description for the thickness and method of bottom slab and roof slab, structural column, lintel, ring beam size and reinforcement, please clarify it.	<i>The question is not clear</i>
58.	Without elevation, the height of roof ridge cannot be confirmed, please clarify it.	<i>The question is not clear</i>
59.	Some internal partition walls cannot be located without axis size, whether the drawings of CAD version can be provided for measurement at your convenience.	<i>The question is not clear</i>
60.	There is no dimension in the sectional drawings of inclined roof truss, so it is impossible to calculate the quantities of timber beams and rafters in the roof truss support system, please clarify it.	<i>This is not part of this tender</i>
61.	The width of aluminum or corrugated iron roof is not marked, please clarify it.	<i>This is not part of this tender</i>
62.	Toilet, roof waterproof requirements, wall plastering hanging steel wire mesh, etc. are not specified, please clarify it.	<i>This is not part of this tender</i>
63.	The unit of item 61.03 (a) in BOQ of lot 3 Section B CT130 AT km151+256 box	<i>The bid lump sum shall include full compensation for</i>

S/N	Issues/Questions	Employer's Responses
	culvert is lump sum. Please clarify whether the payment shall be made on the detailed design drawings or the technical proposal?	<p><i>providing access, which, inter alia, shall include constructing temporary banks, artificial islands and/or cofferdams, their protection, safeguarding and maintenance draining and keeping dry the working areas and draining the excavations within the access, and any incidentals in respect of work to be done below standing water.</i></p> <p><i>75% of the lump sum will be paid when the access has been constructed. The remaining 25% will be paid after the access has been removed.</i></p>
64.	There is no horizontal and vertical sections drawing for Kipumbwi Spur Road (3.7 km) & Pangani Access Road (5.4 km), please clarify it.	Please refer to Clarification No. 28 above.
65.	There is structure box culvert CT61 (KM77.9) in the quantity table of LOT 3 drawing, without detailed structural drawing and there is no such quantity in the BOQ. If there is any, please supplement the drawing.	CT61 (km 77.9) should not be considered.
66.	Please clarify whether the typical cross-section pavement layer (including urban sidewalk) in PDF drawing of LOT 3 is all 50mm SP 12.5	Urban sidewalk is all 50mm SP 12.5.
67.	The top width of black cotton soil cross section is 10.6m, which is inconsistent with the sum (11.6m) of width of each lane and shoulder.	The top with of the black cotton soil cross section is 11.6m
68.	There is no earthwork quantity table and the chainage of black cotton soil subgrade section in road works.	The earthwork quantity is included in Item 36.01(a) of the BoQ
69.	<p>We had completed the project named The Upgrading of Tabora – Nyahua – Chaya - Road (170.2km) to Bitumen Standard, Lot 1; Tabora – Nyahua - Section (85km), Contract No. TRD/HQ/1019/2010/11.</p> <p>According to the Agreement with our parent company, their equipment and plants which are belongs to us and will remain on the site in Tanzania. The parent company will not participate in the bidding process of above mentioned project and LOT 2. We are planning to put some key equipment for above mentioned project. Question: Please confirm</p>	It is a bidder's obligations to identify source of plants and equipment as stipulated in Item 2.6 of Section III: Evaluation and Qualifications Criteria and submit evidence of availability of each of the unit of equipment for Employer's consideration.

S/N	Issues/Questions	Employer's Responses
	if it is acceptable and if we will be disqualified.	
70.	The designs of spur roads are not provided in the bid document.	<i>Please refer to Clarification No. 28 above.</i>
71.	Start and end chainages of the project are not clear identified in the bid documents.	<i>Lot 2 starts at Tungamaa and ends at Pangani Bridge (km 164.75 to 179.05) and it includes Pangani Bridge. Lot 3 starts at Mkange through Mkwaja to Tungamaa (km 73.25 to 164.75).</i>
72.	There is contradiction regarding soil stabilization (C1, C2) in the document whether it should be done on site (in situ) or be done in Plant	<i>Bidders' attention is drawn to the requirements of SS3803 of the Special Specifications.</i>
73.	Confusion of start of the project between the name of project and Lots.	<i>Lot 2 starts at Tungamaa and ends at Pangani Bridge (km 164.75 to 179.05) and it includes Pangani Bridge. Lot 3 starts at Mkange through Mkwaja to Tungamaa (km 73.25 to 164.75).</i>
74.	In order to prepare and submit a competitive bid, we need to do site visit and collect other data/ information. However, due to outbreak of COVID 19 pandemic there are travel restrictions in many countries. We sincerely request you to consider extension of bid due date for at least 60 days from current bid submission date.	<i>Please refer to Clarification No. 25 above.</i>
75.	Please confirm whether there is mistake for the quantity of concrete provided in the BOQ for Pile No. km 92.188, Box culvert CT67 for we believe it is relatively lower than it should be.	<i>Bidders are required to price their Bids based of quantities provided in the BoQ</i>
76.	Could you clarify with us whether the soil excavated from subbase and structural construction can be backfilled?	<i>All materials used for permanent works including backfills shall be used prior to the Engineer's approval</i>
77.	Could you clarify with us whether the customs duties & tax is exempted in this project?	<i>Please refer to Clarification No. 2 above.</i>
78.	Please clarify the meaning of highlighted quantities in BOQ Section B, for example Page 5400, 5500, 5700.	<i>The highlights were not removed un-advertently. Bidders are required to ignore them.</i>

S/N	Issues/Questions	Employer's Responses												
	<p>Standard road signs:</p> <table border="1"> <tr> <td data-bbox="384 264 746 315">(a) Area of sign less than or equal to 1 m²</td> <td data-bbox="746 264 815 315">number</td> <td data-bbox="815 264 932 315">319</td> </tr> <tr> <td data-bbox="384 331 746 383">(b) Area of sign more than 1 m² and less than or equal to 2 m²</td> <td data-bbox="746 331 815 383">number</td> <td data-bbox="815 331 932 383">39</td> </tr> <tr> <td data-bbox="384 398 746 450">(c) Area of sign more than 2 m² and less than or equal to 10 m²</td> <td data-bbox="746 398 815 450">number</td> <td data-bbox="815 398 932 450">36</td> </tr> <tr> <td data-bbox="384 510 746 539">Additional road sign plate</td> <td data-bbox="746 510 815 539">number</td> <td data-bbox="815 510 932 539">20</td> </tr> </table>	(a) Area of sign less than or equal to 1 m ²	number	319	(b) Area of sign more than 1 m ² and less than or equal to 2 m ²	number	39	(c) Area of sign more than 2 m ² and less than or equal to 10 m ²	number	36	Additional road sign plate	number	20	
(a) Area of sign less than or equal to 1 m ²	number	319												
(b) Area of sign more than 1 m ² and less than or equal to 2 m ²	number	39												
(c) Area of sign more than 2 m ² and less than or equal to 10 m ²	number	36												
Additional road sign plate	number	20												
79.	Is water available along the site?	Yes, there are various sources of water including permanent and seasonal rivers. However, it is bidder's responsibility to ensure that water is clean and free from injurious concentration; that is, quality of water should suit for the intended use.												
80.	There is no pay item for sign board in the B.O.Q	Bidders' attention is drawn to Item 12.05 of BOQ												
81.	There is no provision for traffic accommodation in the B.O.Q	Bidders' attention is drawn to the requirements of SS1517 of the Special Specifications												
82.	Will the compensation be ready before the start of the project?	Valuation of properties along construction corridor has been completed. Payment to PAPs will be effected by the Government prior to project commencement.												
83.	The engineer's house lacks Type III drawings	The missing drawings are provided. Please refer Item No. 5 of Addendum No. 2 – Appendix 5												
84.	<div style="border: 1px solid black; padding: 10px; text-align: center;"> <p>Form of Bid Security (Bank Guarantee)</p> </div> <p>_____ [Bank's Name, and Address of Issuing Branch or Office]</p> <p>The Chief Executive, Tanzania National Roads Agency (TANROADS), P. O. Box 11364, Dar es Salaam (hereinafter called "the Employer").</p> <p>Date: _____</p>	Bidders are required to abide to the requirements of the Bidding Documents.												

S/N	Issues/Questions	Employer's Responses
	<p style="text-align: center;">_____</p> <p>[Signature]</p>	
85.	<p>Request for Providing Specifications of Section SS9100</p> <p>There's section SS9100: Mechanically Stabilized Earth (MSE) in the BOQ document "2 Lot 3_Section B_Mkange – Mkwaja – Tungamaa 91.5 km" Section IV-120, but the corresponding specifications are not provided in the Bidding Document, please kindly provide.</p>	<p><i>Please refer to Clarification No. 47 above.</i></p>
86.	<p>The Quantities of some items BOQ are different between the Soft Copy and the Hard Copy which were obtained from your office. For example, Item 42.02 Asphalt Concrete Surfacing, (b) bitumen for asphalt concrete surfacing PG70-22 performance grade bitumen (5.2%), the quantity was indicated as 5500 t and 230 t in the hard Copy of BOQ. But, the Quantity indicated in Soft Copy was 4000 t and 112 t. and Item 42.03 Tack Coat of 30% stable-grade emulsion was not found in the Soft Copy of BOQ.</p> <p>Question: Please confirm which quantity indicated in the Hard Copy and Soft Copy is correct.</p>	<p><i>The quantities provided in the Hard copy shall prevail. Bidders are informed that the Employer shall be not responsible to any alterations/changes of the Bidding documents as a result of use of e-copy.</i></p>