




THE UNITED REPUBLIC OF TANZANIA
MINISTRY OF WORKS AND TRANSPORT



TANZANIA NATIONAL ROADS AGENCY (TANROADS)

UPGRADING OF MNIVATA – NEWALA - MASASI ROAD (160 KM) TO BITUMEN
STANDARD: LOT 1: MNIVATA – MITESA SECTION (100 KM) AND LOT 2: MITESA –
MASASI SECTION (60KM) INCLUDING CONSTRUCTION OF MWITI BRIDGE

TENDER NO. AE/001/2021-22/HQ/W/19


Clarification No. 2 to the Bidding Documents

Date: 5th October 2022

With reference to the questions/queries raised by the prospective bidders and pursuant to Instructions to Bidders ITB 7.1, TANROADS is herewith providing clarifications as follows: -

S/N	Issues/Questions	Clarifications/Responses
1.	<p>We are one of the Prospective Bidders and are keen to submit the bid and working on the tender preparation.</p> <p>As the scope of work involves Construction of roads, we want to undertake a detailed physical site visit to assess the local site conditions and to collect the various information needed from ground – which we feel, are critical to make a responsible offer with accurate pricing and most importantly, be able to complete the project within the stipulated time when awarded.</p> <p>In order to submit a competitive bid after completion of the site visit, we request you to consider extension of bid submission date by 6 weeks from the present due date of September 7, 2022</p>	<p><i>The Employer has considered the request for extension of Bids Submission date. Therefore, the Bids Submission deadline is extended to 27th October 2022.</i></p> <p><i>Please refer Item No. 1 of Addendum No. 1.</i></p>

S/N	Issues/Questions	Clarifications/Responses
2.	According to the quantity of asphalt concrete, we found that the bitumen quantity in the table is not enough, less than half. Please confirm as soon as possible.	<p><i>The Employer confirm that the correct figure shall be 7,460 t for Lot 1 and 4,075 t for Lot 2.</i></p> <p><i>Please refer Item No. 2 for Lot 1 and Item No. 15 for Lot 2 of Addendum No. 1.</i></p>
3.	Please refer to BOQ of LOT 1 - 42.02(b) and LOT2 - 42.01(b) , we think the quantity of bitumen is much less, it shall be twice as much as before.	<p><i>Please refer response to Qn. 2 above</i></p>
4.	<p>Volume I-B- Bills of Quantities</p> <p>“Electrical Installation” “MCL make”</p> <p>Please clarify the exact meaning of MCL</p>	<p><i>MCL make is replaced by British Standard.</i></p> <p><i>Bidders are allowed to supply other equivalent standard products subject to the Engineer’s approval.</i></p> <p><i>Please refer Items No. 3 - 14 for Lot 1 and Items No. 17 - 28 for Lot 2 of Addendum No. 1.</i></p>
5.	<p>Volume I-B- Bills of Quantities</p> <p>“Electrical Installation”</p> <p>Please clarify the implementation standard and voltage class of the cable material</p>	<p><i>The voltage class of the cable is 600/1000 Volt grade and Electrical Installation standard is BS 7671:2018</i></p>
6.	<p>Volume I-B- Bills of Quantities</p> <p>“ICT Installation”</p> <p>Please clarify if the equipment brand is specified as Cisco and if it can be replaced with another brand</p>	<p><i>Bidders are allowed to supply other equivalent standard products.</i></p>
7.	<p>Volume I-C- Employers Requirement</p> <p>Volume I-C, SS.8106 DOCUMENTATION (page 113)</p> <p>The Contractor's Bid shall include specific data sheets and manufacturer details for all types of transformers, feeder pillars, masts, columns, lamps and luminaires that the Contractor will provide.</p> <p>The employer requires the technical data sheet of transformers, feeder pillars, masts, columns, lamps and luminaires, but only the requirements for solar street lamps are given in the</p>	<p><i>Bidders’ attention is drawn to the following standard specifications:</i></p> <ol style="list-style-type: none"> <i>1. BS EN IEC 60076-24 for transformer;</i> <i>2. Feeder pillar should be manufactured with hot dip galvanised BS EN ISO 1461 and comply with BS EN 60529 for protection;</i> <i>3. BS-8100-3 for Masts and columns; and</i> <i>4. 4. BS EN IEC 60598 for Luminaires and lamps</i>

S/N	Issues/Questions	Clarifications/Responses				
	technical specification, please provide the technical requirements for other equipment					
8.	<p>We would like to seek clarification from your office for a comprehensive clarification of the bidding documents:</p> <p>Question</p> <p>The Final Drawings show that there are 63 piles for Mwit Bridge, but the number of piles in BOQ is 95. Please confirm the exact number of piles.</p> <p style="text-align: center;">From Drawings</p>  <p style="text-align: center;">From BOQ</p> <table border="1" data-bbox="292 1055 821 1176"> <tr> <td style="width: 10%;">61.26</td> <td style="width: 70%;">Socketing 600mm diameter piles at least 1m into rock formation of minimum class R3 hardness</td> <td style="width: 10%;">No</td> <td style="width: 10%;">95</td> </tr> </table>	61.26	Socketing 600mm diameter piles at least 1m into rock formation of minimum class R3 hardness	No	95	<p><i>The correct number of piles is 63 instead of 95.</i></p> <p><i>Please refer Item No. 16 of Addendum No. 1.</i></p>
61.26	Socketing 600mm diameter piles at least 1m into rock formation of minimum class R3 hardness	No	95			
9.	<p>VOL IIA- FINAL MATERIALS REPORT 4.6.2 Descriptions of Hard Stone Sources</p> <p>The existing hard stone source in Chipite village, according to the description, the test results indicate that the rock meets all minimum requirements hence can be used for bituminous surfacing, base course and concrete works. From the situation of site investigation, the rock strength is difficult to meet the concrete construction. Please confirm the rock can be used for the bridge construction concrete and other important construction or not.</p>	<p><i>Bidders are informed that it is the Contractor's obligations to search construction materials and carry out all necessary tests to check whether the quality of materials meet the requirements of Technical specifications.</i></p>				
10.	<p>VOL IIA- FINAL MATERIALS REPORT APPENDIX – 7 Test Results for Sand</p>					

S/N	Issues/Questions	Clarifications/Responses
	Please provide fineness modulus of the sand	<i>Bidders are informed that it is the Contractor's obligations to search construction materials and carry out all necessary tests to check whether the quality of materials meet the requirements of Technical specifications.</i>
11.	<p>Volume I-B- Bills of Quantities LOT 1/LOT 2 - 36.02 Fill and improved sub grade layers AND VOL IIA- FINAL MATERIALS REPORT - Table 4-5: Summary of Borrow Pit Locations and Quantities</p> <p>According to the BOQ 36.02 and VOL IIA- FINAL MATERIALS REPORT - Table 4-5, the existing material (in table 4-5) is not enough for fill and improved sub grade layers. Please clarify the other source of the materials</p>	<i>Bidders are informed that it is the Contractor's obligations to search, establish adequate of quantities for construction materials and carry out all necessary tests to check whether the quality of materials meet the requirements of Technical specifications.</i>
12.	<p>PLAN AND LONGITUDINAL I PROFILE</p> <p>Please provide the start and end chainages of Lot 1 and Lot 2.</p>	<p><i>Lot 1: Ch 50+000 – Ch 150+000 Lot 2: Ch 150+000 – Ch 210+000</i></p>
13.	<p>Weighbridge</p> <p>There are two sets of drawing of Weighbridge, Open & covered Ditch, solar street, please clarify which one shall be referred to. Please provide the chainage of weighbridge in Lot 2.</p>	<p><i>Bidders are required to price as per BoQ items 23.08. Location of open and covered ditch shall be instructed by the Engineer during project execution.</i></p> <p><i>Weighbridge in Lot 2 will be located at Ch 180+400</i></p>
14.	<p>Specifications for a Weighbridge Scale</p> <p>Please provide the form of Manufacturer Authorization Letter.</p>	<i>The Manufacturer's Authorization Form (MAF) is not required during bidding stage. The successful Bidder will be required to submit the MAF for review and approval by the Engineer during project execution.</i>
15.	In the BOQ , the quantity of Double Surface Dressing cannot be found, please clarify whether it is missing or include in other items	<i>Quantity for Double Surface Dressing are provided under BoQ Item 44.01 (a). Bidders' attention is drawn to page 12 for Lot 1 and Page 14 for Lot 2.</i>
16.	Kindly request your honor authority to 15 days time extension for bid submission of this tender	<i>Please refer response to Qn. 1 above.</i>
17.	We would sincerely request the employer to extend the deadline of	<i>Please refer response to Qn. 1 above</i>

S/N	Issues/Questions	Clarifications/Responses
	<p>submission for 1 month or more from September 7, 2022 which will enable us to perfect the preparation works</p>	
18.	<p>We would like to request the Specification of pump for the following matters;</p> <p>i) The specifications of pump are not complete</p> <p>Please provide the head and the application of the pumps for both water pump and fire pump.</p>	<p><i>A water pump with minimum capacity of 0.5 hp is required. Fire pump is not part of this tender.</i></p>
19.	<p>we take note that there is omission of the sewage pumps, Fire fighting pumps. Please assist of with the pressure rating of the water supply pumps.</p>	<p><i>Sewage and Firefighting pumps are not part of this tender.</i></p>
20.	<p>Volume I-C- Employers Requirements for Lot 1 & Lot 2</p> <p>SECTION SS.3800: STABILISATION</p> <p>In the "SS3801 SCOPE", there is a description "Mixing of soils and stabilisers shall be done using a stationary mixer. Laying of mixed material shall be laid by means of a self-propelled mechanical spreader and finisher. No in-place mixing will be allowed." However, in the "3803 CONSTRUCTION", there is other description "Construction of cement modified subbase/Base Class C1 and C2 shall be carried out using a mix-in-place construction method with purpose built equipment capable of mixing-in the cement and water in full depth." The two descriptions are different, please clarify the requirement of Stabilised Layer, choosing the stationary mixer or choosing the soil stabiliser machine mix on the road.</p>	<p><i>"Mixing of soils and stabilisers shall be done using a stationary mixer. Laying of mixed material shall be laid by means of a self-propelled mechanical spreader and finisher.</i></p> <p><i>Mix in-place mixing will be allowed only if special mixing machine like Reclaimer stabilizing machine is used."</i></p> <p><i>Otherwise use of other machine like Grader is not allowed.</i></p>
21.	<p>Volume I-B- Bills of Quantities</p> <p>23.08 Concrete Lining for Open Drains</p>	<p><i>Bidders' attention is drawn to the attached drawing for Concrete Lining for Open Drains.</i></p> <p><i>Please refer Item No. 31 of Addendum No. 1.</i></p>

S/N	Issues/Questions	Clarifications/Responses
	In the BOQ, Concrete Lining for Open Drains is situ concrete, please offer the design drawing.	
22.	<p>Set of Drawings - Lot 1-1, Set of Drawings - Lot 1-2 & Set of Drawings Lot 2</p> <p>MTR-MSS-RD-SD-1 : Precast Concrete Lined Trapezoidal Drain</p> <p>The quantity of precast concrete is missing in the BOQ, please clarify whether it is missing or not</p>	<p><i>Bidders are informed that Precast Concrete Lined Trapezoidal Drains are not required.</i></p>
23.	<p>Volume I-B - Bills of Quantities Roadworks – BoQ</p> <p>In the BOQ, the quantity of DOUBLE SURFACE DRESSINGS cannot be found, please clarify whether it is missing or included in other items.</p>	<p><i>Quantity for Double Surface Dressing are provided under BoQ Item 44.01 (a). Bidders' attention is drawn to page 12 for Lot 1 and Page 14 for Lot 2.</i></p>
24.	<p>BDS Cl. 34.2</p> <p>Contractor's proposed subcontracting: Maximum percentage of subcontracting permitted is: 30% of the total Contract Price</p> <p>We request you to allow the Contractor to Sub-Contract at least 50% of the total contract amount.</p>	<p><i>Bidders are required to abide to the requirement of the Bidding Documents.</i></p>
25.	<p>Schedule of Cost indexation "As per the formulae given in the Schedule of Cost indexation price adjustment is applicable on the following components.</p> <p>Local Components:</p> <ol style="list-style-type: none"> 1. Fuel 2. Local Labour 3. Cement 4. Reinforcement steel. <p>Foreign Components:</p> <ol style="list-style-type: none"> 1. Expatriate labour 2. Equipment & Plants 3. Bitumen 4. Structural Steel." 	<p><i>No additional items are allowed. Bidders are required to abide to the requirement of the Bidding Documents.</i></p>

S/N	Issues/Questions	Clarifications/Responses
	<p>We request you to allow the Contractor to submit the foreign & local components for more items in price adjustments based on their bid.</p>	
26.	<p>Special Provisions - Cl. 1.1.49</p> <p>“Laws” means all national (or state) legislation, statutes, ordinances and other laws, and regulations and by-laws of any legally constituted public authority</p> <p>We request you not to modify the original definition of laws as provided in FIDIC GCC.</p>	<p><i>Bidders are required to abide to the requirement of the Bidding Documents.</i></p>
27.	<p>Specific Provision - Cl 4.2.2</p> <p>The first paragraph is replaced in its entirety with: “The Employer shall not make a claim under the Performance Security, except for amounts for which the Employer is entitled under the Contract.”</p> <p>We request you to keep the original GCC clause intact.</p>	<p><i>Bidders are required to abide to the requirement of the Bidding Documents.</i></p>
28.	<p>Contract Data - Cl. 4.2</p> <p>"The Performance Security will be in the form of a “demand guarantee” in the amount(s) of eight (8) percent of the Accepted Contract Amount and in the same currency (ies) of the Accepted Contract Amount.</p> <p>The ES Performance Security will be in the form of a “demand guarantee” in the amount(s) of two (2) percent of the Accepted Contract Amount and in the same currency (ies) of the Accepted Contract Amount."</p> <p>We request you to reduce the Performance security to 5% of the Accepted Contract Amount.</p>	<p><i>Bidders are required to abide to the requirement of the Bidding Documents.</i></p>
29.	<p>Specific Provision - Cl 8.1</p> <p>"The Sub- Clause is replaced in its entirety with the following: “The Engineer shall give a Notice to the Contractor stating the</p>	

S/N	Issues/Questions	Clarifications/Responses
	<p>Commencement Date, not less than 14 days before the Commencement Date.</p> <p>The Notice shall be issued promptly after the Engineer determines the fulfilment of the following conditions:</p> <p>(a) signature of the Contract Agreement by both Parties, and if required, approval of the Contract by relevant authorities of the Country;</p> <p>(b) delivery to the Contractor of reasonable evidence of the Employer's financial arrangements (under Sub-Clause 2.4 [Employer's Financial Arrangements]);</p> <p>(c) except if otherwise specified in the Contract Data, effective access to and possession of the Site given to the Contractor together with such permission(s) under (a) of Sub-Clause 1.13 [Compliance with Laws] as required for the commencement of the Works;</p> <p>(d) receipt by the Contractor of the Advance Payment under Sub-Clause 14.2 [Advance Payment] provided that the corresponding bank guarantee has been delivered by the Contractor;</p> <p>(e) constitution of the DAAB in accordance with Sub-Clause 21.1 and Sub-Clause 21.2 as applicable.</p> <p>Subject to Sub-Clause 4.1 on the Management Strategies and Implementation Plans and the C-ESMP and Sub-Clause 4.8 on the health and safety manual, the Contractor shall commence the execution of the Works as soon as is reasonably practicable after the Commencement Date, and shall then proceed with the Works with due expedition and without delay.””</p>	<p><i>In consideration of provisions stipulated under SCC 21.1 of Particular Conditions- Part A – Contract Data. Bidder's proposal to delete SCC 8.1(e) is acceptable.</i></p> <p>Please refer <i>Item No. 35 of Addendum No. 1.</i></p>

S/N	Issues/Questions	Clarifications/Responses
	<p>We request you to kindly remove the provision regarding appointment of DAAB as pre-requisite for Commencement. This activity can be completed even after the Commencement of the works. Moreover, as per clause 21.1 parties are bound to appoint DAAB within 42 days from date of Signing the Contract. Hence, please delete (e).</p>	
30.	<p>Contract data - CI 8.1</p> <p>Delay damages payable for each day of delay - 0.05% of the Accepted Contract Amount, less Provisional Sum</p> <p>We request you to consider delay damages per day of delay at the rate of 0.05% of value of balance Works less provisional sum.</p>	<p><i>Bidders are required to abide to the requirement of the Bidding Documents.</i></p>
31.	<p>Contract data - CI 8.1</p> <p>Maximum amount of delay damages - 10% of the Accepted Contract Amount</p> <p>We request you to reduce the maximum amount of delay damages to 5% of the Accepted Contract Amount less Provisional sum.</p>	<p><i>Bidders are required to abide to the requirement of the Bidding Documents.</i></p>
32.	<p>Contract data - CI 14.2</p> <p>Total advance payment - 15% of the Accepted Contract Amount less Specified Provisional Sums payable in the currencies and proportions in which the Accepted Contract Amount is payable</p> <p>We request you to provide advance payment of at least 20% of the Accepted Contract Amount less Specified provisional sums.</p>	<p><i>Bidders are required to abide to the requirement of the Bidding Documents.</i></p>
33.	<p>Contract data - CI 14.6.2</p> <p>Minimum Amount of Interim Payment Certificates 2% of the Accepted Contract Amount</p>	<p><i>Bidders are required to abide to the requirement of the Bidding Documents.</i></p>

S/N	Issues/Questions	Clarifications/Responses
	<p>We request you to reduce the minimum amount of IPC to 1% of the Accepted Contract Amount to enhance the cash flow.</p>	
34.	<p>Contract data - Cl 14.7b (i)</p> <p>Period for the Employer to make interim payments to the Contractor under Sub-Clause 14.6 (interim Payment) - 84 days</p> <p>We request you to reduce the duration for payment and provide 90% of the payment within 10 days and balance amount within 56 days from date of submission of statement.</p>	<p><i>Bidders are required to abide to the requirement of the Bidding Documents.</i></p>
35.	<p>Specific provisions & Contract Data</p> <p>"In the first paragraph, delete starting from: "international arbitration" up to the end of (c), and replace with the following: "arbitration. Arbitration shall be conducted as follows: (a) if the contract is with foreign contractors, unless otherwise specified in the Contract Data; the dispute shall be finally settled under the Rules of Arbitration of the International Chamber of Commerce; by one or three arbitrators appointed in accordance with these Rules. The place of arbitration shall be the neutral location specified in the Contract Data; and the arbitration shall be conducted in the ruling language defined in Sub-Clause 1.4 [Law and Language]. (b) If the Contract is with domestic contractors, arbitration with proceedings conducted in accordance with the laws of the Employer's country."</p> <p>Contract Data - Dar es Salaam, Tanzania "</p> <p>"As per 21.6 of specific provisions the place of arbitration shall be a</p>	<p><i>Bidders are required to abide to the requirement of the Bidding Documents.</i></p>

S/N	Issues/Questions	Clarifications/Responses
	<p>neutral location. However, it is mentioned in the Contract data that the place of arbitration as Dar es Salaam which is in Employer's Country.</p> <p>We request you to change the place of arbitration to a neutral country."</p>	
36.	<p>General</p> <p>Utility shifting</p> <p><i>We understand that if any utility shifting is required, the Employer shall obtain necessary permits.</i></p> <p><i>Please Confirm."</i></p>	<p><i>Bidders' attention is drawn to the requirement of Sub-clause 1202 of the Standard Specification for Road Works, 2000.</i></p>
37.	<p>General</p> <p>Tree Cutting</p> <p>"We understand that if any tree cutting is required, the Employer shall obtain necessary permits and clear the trees.</p> <p>Please Confirm."</p>	<p><i>Bidders' attention is drawn to the requirement of Sub-clause 1705 of the Standard Specification for Road Works, 2000.</i></p>
38.	<p>General</p> <p>Environmental Clearances</p> <p>"We understand that, Environmental clearances if any are required the same shall be obtained by the Employer.</p> <p>Please Confirm."</p>	<p><i>Yes. The Employer will obtain environmental clearance of the project as per requirement of the National Laws.</i></p>
39.	<p>"Volume I-A, Section III: Qualification CI - 4.2 (a) - 3"</p> <p>"Specific Construction & Contract Management Experience- If recommended for Lot 1 & 2 A minimum number of four (4) similar contracts each with a value of at least USD 80 million that have been satisfactorily and substantially completed as a prime contractor, joint venture member, management contractor or sub-contractor</p>	<p><i>Bidders are required to abide to the requirement of the Bidding Documents.</i></p>

S/N	Issues/Questions	Clarifications/Responses
	<p>between 1st January 2016 and the bid submission deadline."</p> <p>As per clause No. 4.2 (a) -1 & 2, projects completed from January 2011 would be considered. We understand year 2016 mentioned in CI - 4.2 (a) - 3 is a typo graphical error. Please confirm the year is 2011 and not 2016</p>	
40.	<p>"Volume I-A, Section I & II: Instruction to Bidders & Bid Data Sheet, CI - 19.3"</p> <p>The Bidders shall obtain the Bid Security from a reputable source from an eligible country.</p> <p>"Kindly confirm Bank Guarantee towards Bid Security issued by any reputed bank (Nationalized Bank or Scheduled Bank) in India would be acceptable".</p>	<p><i>The Employer is not familiar with the Bank System in India, hence unable to confirm the Bidder's request. However, Bid Security shall comply with the requirement stipulated under ITB 19.1 of the Instructions to Bidders.</i></p>
41.	<p>"Volume I-A, Section I & II: Instruction to Bidders & Bid Data Sheet CI - 19.3"</p> <p>If an unconditional guarantee is issued by a non-bank financial institution located outside the Employer's Country, the issuing non-bank financial institution shall have a correspondent financial institution located in the Employer's Country to make it enforceable unless the Employer has agreed in writing, prior to Bid submission, that a correspondent financial institution is not required.</p> <p>"We note as per this clause Bid Security can be arranged in the form of Bond from insurance company. Please confirm that our understanding is correct."</p>	<p><i>Bid Security in form of Bond from insurance company will not be accepted. Bidders are informed that Bid Securities shall be in form of unconditional Bank Guarantee issued by financial institutions located in Tanzania. Bid Security issued by financial institution located outside Tanzania shall have a correspondent financial institution located in the Employer's Country to make it enforceable</i></p>
42.	<p>"Volume I-A, Section I & II: Instruction to Bidders & Bid Data Sheet CI - 48"</p>	

S/N	Issues/Questions	Clarifications/Responses
	<p>If the Performance Security furnished by the successful Bidder is in the form of a bond, it shall be issued by a bonding or insurance company that has been determined by the successful Bidder to be acceptable to the Employer.</p> <p>"We note as per this clause Performance Security can be arranged in the form of Bond from insurance company.</p> <p>Please confirm that our understanding is correct."</p>	<p><i>No. The Performance Security in form of Bond from insurance company will not be accepted.</i></p> <p><i>Bidders are informed that the Performance Security shall be in form of unconditional Bank Guarantee.</i></p>
43.	<p>"Volume I-A, Section IX: Particular Conditions Sub Clause - 14.2.1"</p> <p>Advance Payment Guarantee shall be issued by reputable bank or financial institution selected by the Contractor and shall be based on the sample form annexed to the Particular Conditions or in another form agreed by the Employer</p> <p>We note as per this clause Advance Payment Guarantee can be arranged in the form of Bond from insurance company.</p> <p>Please confirm that our understanding is correct.</p>	<p><i>No. Advance Payment Guarantee in form of Bond from insurance company will not be accepted.</i></p> <p><i>Bidders are informed that the Advance Payment Guarantee shall be in form of Unconditional Bank Guarantee.</i></p>
44.	<p>As we are preparing the bidding documents for the Tender No. AE/001/2021-22/HQ/W/19, the following issues need to be clarified by your good office:</p> <p>Please clarify ITB 4.3 regarding of One Bid Per Bidder, does it mean that one Bidder can only select to participate in one bid, either Lot 1 or Lot 2?? If so, it seems to be contradicted with some other clauses in the bidding documents, like Clause 5 in IFB states that Bidders wishing to be considered for award of two Contracts should have, therefore please clarify</p>	<p><i>No. Bidders are allowed to bid for either Lot 1 or Lot 2 or combined Lot 1 & 2. However, Bidders wishing to be considered for award of all two Contracts shall have successfully completed at least four (4) road projects of at least US\$ 80,000,000 of similar nature within the last five (5) years.</i></p> <p><i>Bid Security is required for each lot as per amounts indicated against each lot. Bidders have the option of submitting one Bid Security</i></p>

S/N	Issues/Questions	Clarifications/Responses
	<p>whether the same Bidder can participate in the two Lots separately with separate performance Bid security and two different sets of bidding documents required. Some bidders may not want to combine Lot 1 & 2 together for bid submission as they may not meet the criteria for work experience or other financial requirements, but if they can submit the bid separately for each Lot, they may succeed in winning either of them;</p>	<p><i>for all lots (for the combined total amount of all lots).</i></p>
45.	<p>Please clarify on Clause (q) of the Letter of Bid, can the Bidder propose to use the same list of member of DAAB as proposed by the Employer indicated in the Sub-clause 21.1 of the Particular Conditions?? or the Bidder shall propose his own DAAB members? please clarify. If the bidder is allowed to use the same DAAB member as proposed by the Employer, please provide their CVs as two of the CVs are missing in the bidding documents.</p>	<p><i>Bidders are required to propose different names of DAAB members.</i></p>
46.	<p>Kindly request to issue the revised deadline for submission of bids, so that could prepare the bid guarantee in time</p>	<p><i>Please refer response to Qn. 1 above</i></p>
47.	<p>The unit in the Roadwork- Bills of Quantities 14.01(j) is LS. The unit normally considered as (house unit) x(months) and the quantity of months is 3. Please clarify that the LS shall be considered as (house unit)x(months) with quantity of “3” or not.</p>	<p><i>The unit for payment shall be LS as specified in the Bills of Quantities.</i></p>
48.	<p>The kerbs types of Bills of Quantities 23.01 do not correspond to that listed on the related drawings. Please check the kerb types and clarify that.</p>	<p><i>Please refer response to Qn. 21 above</i></p>
49.	<p>The materials in Bills of Quantities 41.01(a) is C50 Bitumen emulsion, which is unwanted material for Tanzania roadworks projects. And cut-back bitumen is regularly supplied in the market. Shall contractor use MC30 cut-back</p>	<p><i>Bidders are required to abide to the requirement of the Bidding Documents.</i></p>

S/N	Issues/Questions	Clarifications/Responses
	bitumen or MC70 cut-back Bitumen to replace C50 Bitumen emulsion?	
50.	According to Special Specifications SS.3604.01, separate payment will be made for preparation of roadbed in fill and cut as per items 36.02(h), (i) and (ii) of the Bills of Quantities. There are no related items in the Bills of Quantities. Please clarify	<p><i>There are no related items in the Bills of Quantities. This paragraph is removed.</i></p> <p>Please refer <i>Item No. 30 & 31 of Addendum No. 1.</i></p>
51.	<p>For Weighbridge Station drawing of RD643/DS/Y 05:</p> <p>(1) There is no distance of cross bar and dowel bar Whether A252 BRC shall adopt the same type and quantity of bar support which used for the cross bar and dowel bar? Please clarify</p>	<p><i>(1) Bidders' attention is drawn to details on RD643/DS/Y 05 Bidders are required to comply to the specifications and drawings provided in the Bidding Documents</i></p>
52.	We wrote the email to know the submission date for the above tender.	<i>Please refer response to Qn. 1 above.</i>
53.	Reference to your trail email about the addendum issued for "Intention to Extend the Deadline for Submission of Bids" and further to that email we did not receive any addendum regarding the new date for the Bid submission, kindly request you to update on the new bid submission date.	<i>Please refer response to Qn. 1 above.</i>
54.	We would like to know the deadline of the Tender NO. AE/001/2021-22/HQ/W/19. We hope to hearing from you very soon.	<i>Please refer response to Qn. 1 above.</i>
55.	I would like to confirm that the new bid submission date still not announced?	<i>Please refer response to Qn. 1 above.</i>
56.	<p>As per Bidding Document, Volume I-A, Section III - Evaluation and Qualification Criteria under 4.2 (b) Construction Experience in Key Activities (Page 64-66) states that Item (ii) Cement Stabilized sub-base course is one of the key Activities required among the criteria</p> <p>Based on our vast experience, we have observed that nowadays, mechanical modification of natural sub-base is also a preferred</p>	<i>Bidders are required to abide to the requirement of the Bidding Documents.</i>

S/N	Issues/Questions	Clarifications/Responses
	<p>methodology in road construction – as a replacement to Cement Stabilized sub-base course.</p> <p>We have therefore successfully executed several projects where mechanically modified sub-base has constructed.</p> <p>Thus, the purposed of this letter is to request that our experience in construction of sub-base course using mechanical modification also considered as part of the Contractor’s experience for this key activity.</p>	
57.	<p>Please were are writing to request for clarification on the following BoQ items</p> <p>Lot 1: Bill – 4000</p> <p>Section 4100: Prime and Curing Membranes</p> <p>Storm water drainage: 41.01(a) Prime Coat on CRR Base.</p> <p>To this item you have described the prime coat on CRR base, but the CRR base item is not found in the BoQ</p>	<p><i>CRR base course is not required. This item will be used for priming on C2 course.</i></p>
58.	<p>Could you help us confirm if we want to tender for Lot 1 & 2, do we need to prepare tender documents or just 1 tender document.</p>	<p><i>Bidders’ attention is drawn to the requirement of paragraph (f) of the Letter of Bid and other relevant sections of the Bidding Documents.</i></p>